PREVENTIVE MAINTENANCE PROGRAM

# La Marzocco Linea Classic S

12-month preventive maintenance program with 75% off PM labor and trip charge for program participants.

| 12 | 1 | 75% | $37.50/hr | $37.50 |
|---|---|---|---|---|
| MONTH PLAN | SCHEDULED PM VISIT | OFF PM LABOR & TRIP | PROGRAM LABOR RATE | PROGRAM TRIP CHARGE |

| WHEN | VISIT | SERVICES PERFORMED | LABOR |
|---|---|---|---|
| Month 12 | Annual PM | Water test, clean and backflush, group gaskets, diffuser screens, steam valve rebuild, vacuum breakers, safety valve, and full operational checks | 2 hrs |

Standard rates: $150.00/hr labor and $150.00 trip. Program rates: $37.50/hr labor and $37.50 per visit. The trip charge is included in every total in this guide.

PARTS

# PM Kit Contents

| PART | PART # | REPLACED | UNIT COST |
|---|---|---|---|
| Group gasket, 8 mm | H.3.001 | Every 12 months | $3.58 / group |
| Diffuser screen | F.3.040 | Every 12 months | $20.44 / group |
| Steam valve rebuild kit (one per wand) | L165/K | Every 12 months | $39.88 |
| Steam valve anti-suction valve (one per wand) | L192 | Every 12 months | $39.47 |
| Steam boiler vacuum breaker | L190 | Every 12 months | $25.33 |
| Pressure safety valve | B.2.024 | Every 12 months | $99.38 |
| Water test kit | F.9.000.01 | Every 12 months | $11.98 |
| MP paddle valve rebuild kit (per group) *(MP models)* | SA600/K2 | Every 12 months | $250.55 / group |

## INSPECTED, NOT INCLUDED

| PART | PART # | PRICE |
|---|---|---|
| Water level / auto-fill probe | LA052 | $52.86 |
| Contactor, 2 and 3 group | L500 | $210.17 |
| Contactor, 4 group | L510 | $428.79 |
| Pressure-stat, UL | L270/UL | $358.74 |
| Pressure switch membrane kit | L270/1 | $85.82 |

Not included in the totals. Quoted only if replacement is needed.

CONFIGURATION 1 OF 4

# 1 Group

| PART | PART # | REPLACED | QTY | UNIT | EXT. |
|---|---|---|---|---|---|
| Group gasket, 8 mm | H.3.001 | Month 12 | 1 | $3.58 | $3.58 |
| Diffuser screen | F.3.040 | Month 12 | 1 | $20.44 | $20.44 |
| Steam valve rebuild kit (one per wand) | L165/K | Month 12 | 2 | $39.88 | $79.76 |
| Steam valve anti-suction valve (one per wand) | L192 | Month 12 | 2 | $39.47 | $78.94 |
| Steam boiler vacuum breaker | L190 | Month 12 | 1 | $25.33 | $25.33 |
| Pressure safety valve | B.2.024 | Month 12 | 1 | $99.38 | $99.38 |
| Water test kit | F.9.000.01 | Month 12 | 1 | $11.98 | $11.98 |
| MP paddle valve rebuild kit (per group) *(MP only)* | SA600/K2 | Month 12 | 1 | $250.55 | $250.55 |

STANDARD · 12-MONTH TOTAL

**$431.91**



Parts $319.41 · Labor $75.00 · Trip $37.50

MP · 12-MONTH TOTAL

**$682.46**



Parts $569.96 · Labor $75.00 · Trip $37.50

Parts Labor Trip

**You save $337.50 on labor and trip**

CONFIGURATION 2 OF 4

# 2 Group

| PART | PART # | REPLACED | QTY | UNIT | EXT. |
|---|---|---|---|---|---|
| Group gasket, 8 mm | H.3.001 | Month 12 | 2 | $3.58 | $7.16 |
| Diffuser screen | F.3.040 | Month 12 | 2 | $20.44 | $40.88 |
| Steam valve rebuild kit (one per wand) | L165/K | Month 12 | 2 | $39.88 | $79.76 |
| Steam valve anti-suction valve (one per wand) | L192 | Month 12 | 2 | $39.47 | $78.94 |
| Steam boiler vacuum breaker | L190 | Month 12 | 1 | $25.33 | $25.33 |
| Pressure safety valve | B.2.024 | Month 12 | 1 | $99.38 | $99.38 |
| Water test kit | F.9.000.01 | Month 12 | 1 | $11.98 | $11.98 |
| MP paddle valve rebuild kit (per group) *(MP only)* | SA600/K2 | Month 12 | 2 | $250.55 | $501.10 |

STANDARD · 12-MONTH TOTAL

**$455.93**



Parts $343.43 · Labor $75.00 · Trip $37.50

MP · 12-MONTH TOTAL

**$957.03**



Parts $844.53 · Labor $75.00 · Trip $37.50

Parts Labor Trip

**You save $337.50 on labor and trip**

CONFIGURATION 3 OF 4

# 3 Group

| PART | PART # | REPLACED | QTY | UNIT | EXT. |
|---|---|---|---|---|---|
| Group gasket, 8 mm | H.3.001 | Month 12 | 3 | $3.58 | $10.74 |
| Diffuser screen | F.3.040 | Month 12 | 3 | $20.44 | $61.32 |
| Steam valve rebuild kit (one per wand) | L165/K | Month 12 | 2 | $39.88 | $79.76 |
| Steam valve anti-suction valve (one per wand) | L192 | Month 12 | 2 | $39.47 | $78.94 |
| Steam boiler vacuum breaker | L190 | Month 12 | 1 | $25.33 | $25.33 |
| Pressure safety valve | B.2.024 | Month 12 | 1 | $99.38 | $99.38 |
| Water test kit | F.9.000.01 | Month 12 | 1 | $11.98 | $11.98 |
| MP paddle valve rebuild kit (per group) *(MP only)* | SA600/K2 | Month 12 | 3 | $250.55 | $751.65 |

STANDARD · 12-MONTH TOTAL

**$479.95**



Parts $367.45 · Labor $75.00 · Trip $37.50

MP · 12-MONTH TOTAL

**$1,231.60**



Parts $1,119.10 · Labor $75.00 · Trip $37.50

Parts Labor Trip

**You save $337.50 on labor and trip**

CONFIGURATION 4 OF 4

# 4 Group

| PART | PART # | REPLACED | QTY | UNIT | EXT. |
|---|---|---|---|---|---|
| Group gasket, 8 mm | H.3.001 | Month 12 | 4 | $3.58 | $14.32 |
| Diffuser screen | F.3.040 | Month 12 | 4 | $20.44 | $81.76 |
| Steam valve rebuild kit (one per wand) | L165/K | Month 12 | 2 | $39.88 | $79.76 |
| Steam valve anti-suction valve (one per wand) | L192 | Month 12 | 2 | $39.47 | $78.94 |
| Steam boiler vacuum breaker | L190 | Month 12 | 1 | $25.33 | $25.33 |
| Pressure safety valve | B.2.024 | Month 12 | 1 | $99.38 | $99.38 |
| Water test kit | F.9.000.01 | Month 12 | 1 | $11.98 | $11.98 |
| MP paddle valve rebuild kit (per group) *(MP only)* | SA600/K2 | Month 12 | 4 | $250.55 | $1,002.20 |

STANDARD · 12-MONTH TOTAL

**$503.97**



Parts $391.47 · Labor $75.00 · Trip $37.50

MP · 12-MONTH TOTAL

**$1,506.17**



Parts $1,393.67 · Labor $75.00 · Trip $37.50

Parts Labor Trip

**You save $337.50 on labor and trip**

SUMMARY

# 12-Month PM Cost by Configuration

| CONFIGURATION | PARTS | LABOR | TRIP | STANDARD TOTAL | MP TOTAL |
|---|---|---|---|---|---|
| 1 Group | $319.41 | $75.00 | $37.50 | **$431.91** | **$682.46** |
| 2 Group | $343.43 | $75.00 | $37.50 | **$455.93** | **$957.03** |
| 3 Group | $367.45 | $75.00 | $37.50 | **$479.95** | **$1,231.60** |
| 4 Group | $391.47 | $75.00 | $37.50 | **$503.97** | **$1,506.17** |

## GOOD TO KNOW

- At least one PM visit per year is recommended.
- Labor and trip are 75% off standard rates and are included in every total.
- Parts are list price. Items that are only inspected are quoted if they need replacing.
- Installation is not included in PM pricing.